

RINCIAN RENCANA ANGGARAN BIAYA (RAB)

Pekerjaan : Area Hyrox Rooftop RS Edelweiss Bandung
Pemilik : RS Edelweiss
Lokasi : Kota Bandung
Tahun : 2026



NO	NAMA PEKERJAAN	VOLUME	SATUAN	HARGA SATUAN	JUMLAH
A	PEK. AREA RUMPUT SINTETIS				
	PEK. PERSIAPAN				
	Pek. Bongkar Kolom Beton	3,2	m3	Rp 107.865	Rp 345.168
	JUMLAH PEK. PERSIAPAN				Rp 345.168
	AREA RUMPUT SINTETIS				
	Pas. Draincell 30 mm	0,6	m2	Rp 222.750	Rp 133.650
	Pas. Rumput Sintetis	234,3	m2	Rp 270.000	Rp 63.261.000
	JUMLAH PEK. RUMPUT SINTETIS				Rp 63.394.650
B	PEKERJAAN STRUKTUR				
	Pek Galian				
	Pek. Galian Sloof	12,1671	m3	Rp 107.865	Rp 1.312.404
	Pek. Urugan Tanah Kembali	2,43342	m3	Rp 125.550	Rp 305.516
	Sloof 15 x 25				
	Bekisting 2x Pakai	60,192	m2	Rp 160.070	Rp 9.634.933
	Pembesian (4D10 - D8-150)	650,364	Kg	Rp 19.575	Rp 12.730.875
	Beton Cor K-250	9,042	m3	Rp 1.426.950	Rp 12.902.482
	Pelat Lantai (Slab)				
	Bekisting 2x pakai	111,8	m2	Rp 160.070	Rp 17.895.826
	Pembesian Wiremesh (M10)	877,63	Kg	Rp 19.575	Rp 17.179.607
	Beton Cor K-225	13,416	m3	Rp 1.300.475	Rp 17.447.176
	Kolom 15 x 15 (K2)				
	Bekisting	72,864	m2	Rp 160.070	Rp 11.663.340
	Pembesian (4D10 - D8-150)	624,855	Kg	Rp 19.575	Rp 12.231.537
	Beton Cor K-250	3,0603	m3	Rp 1.426.950	Rp 4.366.895
	Balok 15 x 25 (B1)				
	Bekisting	43,428	m2	Rp 160.070	Rp 6.951.520
	Pembesian (4D10 - D8-150)	269,808	Kg	Rp 19.575	Rp 5.281.492
	Beton Cor K-250	2,079	m3	Rp 1.426.950	Rp 2.966.629
	JUMLAH PEK. STRUKTUR				Rp 132.870.233
C	ARSITEKTUR				
	Pas. Kanopi Rangka Hollow + Atap Kaca Abu (Area Depan)	20	m2	Rp 877.500	Rp 17.550.000
	Kanopi Zincalume + Rangka (Area Belakang)	58,5	m2	Rp 607.500	Rp 35.538.750
	Pintu Kaca Double (Area Masuk)	2	Set	Rp 6.245.452	Rp 12.490.904
	Jendela Kaca (Area Depan & Belakang)	2	Set	Rp 4.137.750	Rp 8.275.500
	Pek. Dinding Bata Ringan t=10 cm	250	m2	Rp 124.781	Rp 31.195.125
	Pek. Plester Dinding	500	m2	Rp 75.492	Rp 37.746.000
	Pek. Acian	500	m2	Rp 63.221	Rp 31.610.250
	Pek. Pengecatan Dinding (Putih)	195,7	m2	Rp 84.027	Rp 16.444.025
	Pek. Pengecatan Dinding Semen Ekspose + Tulisan	89,6	m2	Rp 71.979	Rp 6.449.345
	Pek. Pengecatan Tulisan (Trust The Process)	89,6	m2	Rp 13.500	Rp 1.209.600
	Pek. Lantai Ekspose Semen	67,4	m2	Rp 51.729	Rp 3.486.555
	Pintu (P1)	3	Unit	Rp 2.774.076	Rp 8.322.228
	Pas. Plafon	215	m2	Rp 158.867	Rp 34.156.330
	HT 60 x 60 Atlas Grey	53,2	m2	Rp 661.500	Rp 35.191.800
	Keramik Dinding KM 20 x 20	23,7	m2	Rp 746.624	Rp 17.694.995
	INTERIOR & MEUBELAIR				
	Cermin Gym	9	Unit	Rp 2.061.500	Rp 18.553.500
	Cubicle Phenolyc Partisi Toilet	14	Unit	Rp 2.362.500	Rp 33.075.000
	Signage Acrylic (Edelweiss Sport & Rehabilitation)	2	Set	Rp 6.885.000	Rp 13.770.000

NO	NAMA PEKERJAAN	VOLUME	SATUAN	HARGA SATUAN	JUMLAH
	Signage Acrylic Logo Edelweiss	1	Set	Rp 6.345.000	Rp 6.345.000
	Sticker (Edelweiss Sport & Rehabilitation)	1,7	m2	Rp 202.500	Rp 344.250
	Sofa 3 Seater	1	Unit	Rp 9.247.500	Rp 9.247.500
	Sofa Single (Dengan Senderan)	1	Unit	Rp 3.172.500	Rp 3.172.500
	Sofa Single (Tidak Dengan Senderan)	2	Unit	Rp 2.025.000	Rp 4.050.000
	Meja Bundar	2	Unit	Rp 4.725.000	Rp 9.450.000
	Set Kursi dan Meja Outdoor	4	Set	Rp 3.750.000	Rp 15.000.000
	Sofa Bench	4	Unit	Rp 877.500	Rp 3.510.000
	Meja Kasir + etalase	1	Unit	Rp 6.750.000	Rp 6.750.000
	Backdrop HPL Motif Stainless	15,2	m2	Rp 2.160.000	Rp 32.832.000
	Backdrop Toilet	4,6	m2	Rp 2.160.000	Rp 9.936.000
	Signage Toilet	1	Set	Rp 1.687.500	Rp 1.687.500
	Barikade Pembatas Hyrox	15	m'	Rp 595.125	Rp 8.926.875
	Lantai Gym Vinyl	70,8	m2	Rp 307.024	Rp 21.737.282
	ATAP				
	Rangka Baja Ringan	75,03	m2	Rp 290.920	Rp 21.827.694
	Atap Zinalume ex. Fumira	79,03	m2	Rp 504.974	Rp 39.908.095
	Pas. Aluminium Foil Atap	79,03	m2	Rp 74.460	Rp 5.884.579
	Rangka Hollow 4x6	2,6	m2	Rp 775.000	Rp 2.015.000
	Kaca Tempered 6 mm	7,94	m2	Rp 802.921	Rp 6.375.193
JUMLAH PEK. ARSITEKTUR					Rp 571.759.373
D	MEP				
	AREA ELEKTRIKAL				
	Instalasi Saklar Tunggal panasonic	6	Titik	Rp 89.505	Rp 537.030
	Instalasi Saklar Seri Double panasonic	6	Titik	Rp 122.683	Rp 736.096
	Instalasi Stop Kontak Setara Panasonic	8	Titik	Rp 463.050	Rp 3.704.400
	Instalasi Lampu Downlight	36	Titik	Rp 447.525	Rp 16.110.900
	INSTALASI AIR BERSIH				
	Pipa PVC 1/2" (Air Bersih Toren ke Keran)	10	m	Rp 75.452	Rp 754.515
	Pipa PVC 1" (Air Sumur ke Toren)	9	m	Rp 84.767	Rp 762.899
	Fitting dan Support instalasi pemipaan	1	Ls	Rp 216.294	Rp 216.294
	INSTALASI AIR BEKAS & AIR HUJAN				
	Pipa PVC 2" (Air Bekas)	10	m	Rp 75.452	Rp 754.515
	Pipa PVC 4" (Hujan)	6,6	m	Rp 84.767	Rp 559.459
	PEK. SANITAIR				
	Pek. Instalasi Kloset Duduk Setara Volk	6	Bh	Rp 2.049.300	Rp 12.295.800
	Pek. Instalasi Urinoir	3	Bh	Rp 1.644.300	Rp 4.932.900
	Pek. Instalasi Shower	8	Bh	Rp 1.975.000	Rp 15.800.000
	Pek. Instalasi Wastafel	7	Bh	Rp 1.900.000	Rp 13.300.000
	Pek. Instalasi Kran	7	Bh	Rp 345.000	Rp 2.415.000
	Floor Drain	2	Unit	Rp 430.000	Rp 860.000
JUMLAH PEK. MEP					Rp 73.739.807
TOTAL					Rp 842.109.232

Bandung, Maret 2026

GAMPAWORKS